

# Status & Update European XFEL


*Wissenschaftlicher Ausschuss DESY*

7. September 2010

Thomas Tschentscher

*[thomas.tschentscher@xfel.eu](mailto:thomas.tschentscher@xfel.eu)*


---



- **Status European XFEL**
  - Overview
  - Accelerator
  - X-ray systems & scientific instruments
  - Civil construction
- **Project update**
  - New developments
  - Adaption of design
  - Project timeline
- **Summary**







International research infrastructure for the application of soft & hard X-ray FEL radiation in user experiments by a multi-disciplinary science community.



see [www.xfel.eu](http://www.xfel.eu) for details




# VUV – X-ray Free-electron lasers




**FEL radiation**


1-100's fs  
max.  $10^{14}$  phts/pulse  
coherent



**Synchrotron radiation**

30-80 ps  
max.  $10^9$  phts/pulse  
incoherent





## Reaction chemistry

- time-resolved atomic structures
- catalysts, photo-chemistry
- develop new processes & products




## Complex materials

- combine atomic & electronic structure
- functional materials, magnetism
- develop new materials

## Life sciences

- atomic structure → function
- mol., complexes, cells
- develop new treatments

Nuclear pore  
complex



... these are only few examples out of a long list of research problems in many scientific disciplines from biology via physics to geo-sciences

## The international process

- Technical design report published 2001/02
- In 2003 first steering committee meetings
- Project start in June 2008
- Signing convention & GmbH creation in Nov 2009
- Currently 11 signatories / 8 shareholders
- France & Italy are expected to join still 2010.
- Spain has confirmed its interest to join, likely in spring 2011. Further countries have indicated interest to join or become associated with the project.




Signing of convention, Nov 2009,  
Hamburg City hall

## Construction project

- Total cost ~1.1 billion EUR
- The German shareholder DESY enabled the preparation, acts as a host laboratory and is largely involved in accelerator construction & operation.


## Operation phase

- Initially 15 years with annual budget ~75 M€






# Accelerator Complex



**100 accelerator modules**



**800 accelerating cavities**  
**1.3 GHz / 23.6 MV/m**



**Injector**  
**Bunch Compressor**

**Main Linac**

**25 RF stations**  
**5.2 MW each**





**Collimation**

**Beam Distribution**

**Undulators**

**Length [m]**





Accelerators | Photon Science | Particle Physics  
Deutsches Elektronen-Synchrotron  
A Research Centre of the Helmholtz Association



DESY, V401, 22603 Hamburg, Germany

[Click here and type recipient's address ]

Purchaser  
Purchasing Projects  
Tel. +49 40 8998-1539  
Fax +49 40 8998-4009  
Email: purchasing.v401@desy.de

July 2, 2009

**CALL FOR TENDER  
EUROPEAN NEGOTIATED PROCEDURE  
DESY- Reference No.: EV 012-09-XFEL**

**Supply of 1.3 GHz Niob Resonators for XFEL**

Dear Sir or Madam,

With reference to the VOLIA (Conditions concerning Contracts for Supplies and Services, Part A), as well as the accompanying documents, we herewith request you to submit your best offer in accordance with and subject to the following requirements and guidelines:

**1. PREAMBLE**

In this document, the following shall apply:

**DESY** refers to the Deutsches Elektron-Synchrotron in the Helmholtz-Gemeinschaft, Hamburg, Germany.

**INFN** refers to the Istituto Nazionale di Fisica Nucleare, headquartered in Frascati (Rome) Italy.


**Orderer** refers to the institution allocating the contract (DESY), or the institutions supervising the cavity production (DESY and/or INFN).

**Contractor** refers to the company (or companies) executing the cavity production. The possible Contractors must be previously qualified through the successful production and delivery of superconducting

**DESY Deutsches  
Elektronen-Synchrotron**  
Notkestrasse 85  
22607 Hamburg  
Germany  
Tel. +49 40 8998-0  
Fax +49 40 8998-3282

**Postal address**  
22603 Hamburg  
Germany  
**Locations of DESY**  
Hamburg  
Zeuthen/Brandenburg


**Directorate**  
Dr. R. Brinkmann  
Prof. Dr. H. Dösch  
(Chairman)  
Prof. Dr. J. Mnich  
C. Socher  
Prof. Dr. E. Weckert  
Dr. U. Gensch  
(Representative of Directors  
in Zeuthen)



- **Cavity Call for Tender was published on July 2<sup>nd</sup>, 2009.**
- **Production and preparation in industry.**
- **Contracts to be allocated by DESY and supervision of cavity production by DESY/INFN.**
- **Cost much higher than planned**
- **Contracts are awarded**



# Cavity String & Module Assembly





Using experience gained at DESY and results of industrial studies, the assembly facility for all 100 XFEL modules will be set up at the CEA-Saclay site.

CEA (IRFU), CIEMAT, DESY, INFN-Milano, LAL Orsay, Swierk take the responsibility for the cold linac.




# Infrastructure for Module Assembly



- Major part of the civil engineering and general equipments was done; big assembly tools ordered and to be delivered.



# XFEL Accelerator Module Prototypes




**Call for tender  
European XFEL cold masses  
in preparation**





## XFEL RF Power Coupler





- *TTF3 coupler type*







- **LAL Orsay** has taken over the responsibility for the XFEL RF power **coupler production**.
- **Conditioning** of the couplers will take place at LAL Orsay.
- The **coupler interlock** system was developed and will be **contributed by DESY**.

# Accelerator Module Test Facility (AMTF) Including Single Cavity Test Facility



- AMTF Civil Construction finished
- Infrastructure installation started
- First **cavity tests** spring 2011
- Commissioning of **module test facility** foreseen for 4/2011
- Major cryogenic contributions from Russia and Poland
- **Waveguide assembly and test**





- civil construction (tunnels/halls) foresees 5 undulator locations
- straight sections for undulators sufficiently long for options
  - ➔ **2-colors and afterburners**
  - ➔ **self-seeding or laser-seeding or laser-e-beam manipulation**




**SASE 1**

- hybrid magnets; gap tunable (min. 10 mm)
- 165 m magnetic length & 140 m optional
- $\lambda_{\text{und}} 35.6 \text{ mm} \Rightarrow \sim 4600$  periods
- optimized for 12.4 keV (K=3.3)

**SASE 2**

- hybrid magnets; gap tunable (min. 10 mm)
- 210 m magnetic length & 100 m optional
- $\lambda_{\text{und}} 48 \text{ mm} \Rightarrow \sim 4400$  periods
- gap-tunable for 3.1 to 12.4 keV (K=2.8 – 6.1)




Parameter	Unit	SASE 1	SASE 2	
Photon energy	keV	12.4	12.4	3.1
Pulse energy	mJ	2	2	8
Bandwidth	%	0.08	0.08	0.18
Divergence	$\mu\text{rad}$	1.0	0.9	3.4
Source size	$\mu\text{m}$	70	85	55
Polarization		hor. lin.	horizontal linear	

Ref: TDR 2006/Startup


## Single Particles, Clusters, and Biomolecules (SPB)

- Structure of atomic clusters, bio-molecules, virus particles, cells
- Time-resolved diffraction from gas molecules
- Techniques: CXI, particle injection; 3-12 keV




## Materials Imaging & Dynamics (MID)

- Structure & dynamics of nanoscale objects
- Techniques: CXI, Bragg-diff., XPCS (SAXS, large Q); 5-25 keV



## Femtosecond X-ray Experiments (FXE)

- Time-resolved atomic structure of liquid & hard matter
- Techniques: Diffraction, XAS, IXS; solids & liquids; 5-18 keV




## High Energy Density Matter (HED)

- Structure & dynamics of matter under extr. conditions
- Techniques: Scattering, emission; 3-18 keV

## Soft x-ray source &amp; beam properties

## SASE 3

- hybrid magnets; gap tunable (min. 10 mm)
- 105 m magnetic length & 60 m optional
- $\lambda_{\text{und}}$  65 mm  $\Rightarrow$   $\sim$ 1600 periods
- gap-tunable for 0.8 to 3.1 keV and 0.25 to 1.0 keV (K=3.3 – 8.6)




Parameter	Unit	17.5 GeV		10 GeV	
Photon energy	keV	3.1	0.8	1.0	0.25
Pulse energy	mJ	8	13	$\sim$ 10	15
Bandwidth	%	0.2	0.3	$\sim$ 0.3	0.65
Divergence	$\mu$ rad	3.4	11.4	$\sim$ 10	18
Source size	$\mu$ m	60	70	$\sim$ 70	90
Polarization		horizontal linear		horizontal linear	

Ref: TDR 2006/Startup



### Small Quantum Systems (SQS)

- Investigation of atoms, ions, molecules and clusters in intense fields and non-linear phenomena
- Techniques: electron & ion spec., emission; 0.27-3 keV





### Soft x-ray Spectroscopy & Coherent Scattering (SCS)


- Structure & dynamics of nano-objects and magnetic structures
- Structure of non-reproducible biological objects
- Techniques: electron spec., XAS, IXS, CXI; 0.27-2 keV




# High repetition rate challenge



# Civil construction




- shaft buildings (5)
- experiments hall (1)
- tunnel (11)
- surface buildings (>10)





# DESY-Bahrenfeld - Baugrube Injektorkomplex





# Construction site webcams 24. August 2010



**DESY-Bahrenfeld**




**Schenefeld Ost**



**Osdorfer Born**



**Schenefeld West**



## **Herstellung der Tunnel im Vortriebsverfahren**

- Schenefeld ⇒ Osdorfer Born
- Osdorfer Born ⇒ DESY-Bahrenfeld (Juni 2011)
- „Fächer“ aus 5 Tunneln unter Schenefelder Gelände

**5777 m Tunnel, Tiefe: 6 m – 38 m**



**2 Tunnelbohrmaschinen: TBM 1 (5,30 m Ø) und TBM 2 (4,60 m Ø)**

- Hydromixschild für heterogene Baugründe
- „TULA“ – TVM(5,30 m): 3 Abschnitte, 1 Umsetzung, 1 Durchfahrt  
Durchmesser: 5,30 m (Tunnel innen), 6,17 m (TBM außen)
- TVM(4,50 m): 8 Abschnitte, 4 Umsetzungen, 3 Durchfahrten  
Durchmesser: 4,60 m (Tunnel innen), 5,48 m (TBM außen)


**1 zentrale Separieranlage**



# Tunnel boring sequence



# Tunnelbohrmaschine S-544 – Im Werk






# Tunnelbohrmaschine S-544




**Transport nach Schenefeld am 19. Mai 2010**



# „TULA“ – Tunnel- und Bohrertaufe




# „TULA“ im Einsatz nach ca. 100 m



**Blick auf das Ende des Nachläufers und die Tunnelbahn am 27. Juli 2010**



# TULA arrives at XS1 (first tunnel completed)







**Office and Lab building  
with lecture hall, seminar  
rooms, library, etc.**




**from 2014/2015: user  
operation of beam lines &  
instruments; research  
~300 – 350 Personen**

**on top of underground  
experiment hall**


Architekturbeispiel

- **Status European XFEL**
  - Overview
  - Accelerator
  - X-ray systems & scientific instruments
  - Civil construction
- **Project update**
  - New developments
  - Adaption of design
  - Project timeline
- **Summary**


# First short-wavelength FEL user facility : FLASH



2001



2005






H. Wabnitz et al., Nature 420, 482 (2002)

H. Chapman et al., Nature Phys. 2, 839 (2006)



# First hard X-ray facility: LCLS




## Photo-Injector Test Stand in DESY-Zeuthen


- Photo injector R&D
- Test and pre-conditioning of FLASH and XFEL photo injectors
- Collaborations with MBI (lasers), Rossendorf, HZB & others (cw-gun)




Measured projected emittance  
versus bunch charge



Flat-Top laser with sharp edges



## Under study: New parameter set accelerator



	Unit	TDR/startup	New Set
Electron Energy for 0.1 nm	GeV	17.5	14
Bunch charge	nC	1	0.02 – 1
Peak current	kA	5	2 - 5
Slice emittance	mm mrad	< 1.4	0.4 - 1.0
Slice energy spread	MeV	1.5	4 - 2
Shortest SASE wavelength	Nm	0.1	0.05
Pulse repetition rate	Hz	10	10
Bunch repetition rate	MHz	5	4.5
Bunches per pulse		3000	2700





## Accelerator parameter sets






	Charge	nC	1	0.5	0.25	0.1	0.02
Gun	<b>Peak Current</b>	<b>A</b>	<b>49.8</b>	<b>33.2</b>	<b>18.4</b>	<b>8.3</b>	<b>1.8</b>
	<b>Slice Emittance</b>	$\mu\text{m}$	<b>1</b>	<b>0.7</b>	<b>0.5</b>	<b>0.32</b>	<b>0.2</b>
	<b>Slice Energy Spread (LH)</b>	<b>keV</b>	<b>20.0</b>	<b>18.2</b>	<b>15.3</b>	<b>9.8</b>	<b>3.6</b>
Undulator	Peak Current	kA	5.0	4.0	3.0	2.5	2.0
	Slice Emittance	$\mu\text{m}$	1.05	0.77	0.60	0.42	0.40
	Slice Energy Spread	MeV	2.0	2.2	2.5	2.9	4.1

- Emittance and energy spread numbers based on best present knowledge and leave room for eventual improvement
- Complete accelerator (diagnostics, LLRF, ...) has been designed for 1 nC charge, impact of lower charges (signal to noise, stability, ...) on accelerator systems under study

# Photon energy ranges







# FEL performance (I) – pulse energy







## FEL performance (II) – bunch charge dependence




# Saturation lengths



# Electron beam bunch pattern


## Electron bunch delivery

- due to pulsed RF



## Advantages for user operation


- enables stabilization by intra-bunch feedback
- higher flexibility of operation for simultaneous user experiments
- large number of delivered FEL pulses
  - **Combination of peak & average brilliance**






## European XFEL accelerator & beam delivery enables flexible patterns

- operate sc-accelerator in (almost) steady-state mode
- select bunch pattern by fast kicking
- bunch delivery pattern determined by user experiment
  - **single pulses**
  - **medium repetition rate (10 – 100 kHz)**
  - **high repetition rates (1 → 4.5 MHz)**
  - **special fills**
    - logarithmic distribution
    - shorter distances (~700 ps – 220 ns)




## Fresh bunch technique


- FEL process spoils energy spread of electron bunch
- suppress FEL process by adding removeable betatron oscillation
- fast kicker for 5 Mhz pattern
  
- modes for one undulator
  - requires  $L_{\text{und}} \gg L_{\text{sat}}$
  - 2 photon energies (2-colors)
  - Angular separated beams (*canted-mode*;  $\sim 10 \mu\text{rad}$ )
  
- modes for several undulators
  - decouple operation



## Timeline European XFEL







**European XFEL construction now progresses in all areas. Early experiments are scheduled for 2015.**



**Civil construction so far goes well and did neither accumulate delays nor large extra-cost. Next step is tendering and awarding of surface buildings.**




**Recent experience LCLS shows great potential for future FEL applications. Bunch charge and variable compression are additional parameters. Users like high stability and fast change of settings. First hard x-ray FEL experiments this September.**



**Design of European XFEL is currently updated. In contrast to others it will be a multi-user facility from the start. For this purpose several FEL sources and independent x-ray beamlines are built. Bunch delivery system and pulse train operation support specific delivery schemes.**

**the end**




# Diffraction limited FEL radiation



$$\text{Peak brilliance} = \frac{10^{12}(X) - 10^{14}(sX)}{\Delta_x \Delta_x \Delta_y \Delta_y' \times \text{bandwidth} \times \Delta_t}$$






*Number of photons*  
*bandwidth*

$6 \times 10^{-11} \text{m}(X) \sim \lambda/2$       $100 \text{ fs eV}(X) \sim 25\hbar$





# Temporal x-ray beam properties



Simulations performed by E. Saldin, E. Schneidmiller and M. Yurkov

simplified

$$\tau_c = \frac{1}{2c} \frac{\lambda^2}{\Delta\lambda}$$

more complete

$$g_1(\mathbf{\epsilon}, t-t') = \frac{\langle E(\mathbf{\epsilon}, t) E^*(\mathbf{\epsilon}, t') \rangle}{\left[ \langle |E(\mathbf{\epsilon}, t)|^2 \rangle \langle |E(\mathbf{\epsilon}, t')|^2 \rangle \right]^{1/2}}$$

quasi-  
stationary  $\rightarrow$ 

$$\tau_c = \int_{-\infty}^{+\infty} g_1(\tau) d\tau$$

## European XFEL


SASE1/SASE2 : 12.4 keV

SASE4: 3.1 keV

Saturation curve

Simulations performed by  
E. Saldin, E. Schneidmiller  
and M. Yurkov

G. Geloni et al.,  
New J. Phys. 12, 035021 (2010)



simplified

$$\xi_t = \frac{\lambda L}{2\pi\sigma}$$


more complete

$$\gamma_1(\boldsymbol{\kappa}_\perp, \vec{r}_\perp') \Rightarrow \frac{\langle E(\boldsymbol{\kappa}_\perp) E^*(\boldsymbol{\kappa}_\perp') \rangle}{\left[ \langle |E(\boldsymbol{\kappa}_\perp)|^2 \rangle \langle |E(\boldsymbol{\kappa}_\perp')|^2 \rangle \right]^{1/2}} \longrightarrow \xi_t(\boldsymbol{\kappa}_\perp) \Rightarrow \int_{-\infty}^{+\infty} \gamma_1(\boldsymbol{\kappa}_\perp, \Delta r_\perp) d\Delta r_\perp$$

Degree of transverse coherence



$$\zeta = \frac{\iint |\gamma_1(\boldsymbol{\kappa}_\perp, \vec{r}_\perp')|^2 \langle I(\boldsymbol{\kappa}_\perp) \rangle \langle I(\boldsymbol{\kappa}_\perp') \rangle d\vec{r}_\perp d\vec{r}_\perp'}{\left[ \langle I(\boldsymbol{\kappa}_\perp) \rangle d\vec{r}_\perp \right]^2}$$

European XFEL


TDR conditions:  $\hat{\varepsilon} \cong 2.6$ improved cond.:  $\hat{\varepsilon} < 1.0$ Simulations performed by E. Saldin,  
E. Schneidmiller and M. YurkovG. Geloni et al.,  
New J. Phys. 12, 035021 (2010)




# Transverse x-ray beam properties




**undulator  
entrance**



**half-way  
undulator**



**full  
saturation**




**12.4 eV**



Simulations performed by S. Reiche (UCLA, now SLS)

■ for hard x-rays diffraction limited beams are crucial



# Particle injection



Sample delivery & diagnostics




$10^5 \text{ p/cm}^3 = 2.5 \times 10^{-5} \text{ p}/(250 \mu\text{m}^3)$   
 $200 \text{ m/s} \rightarrow \text{traverse } 1 \mu\text{m} : 5 \text{ ns}$



**Mass spectrum**


data courtesy H. Chapman, J. Hajdu & coworkers

# 2D pixel detector developments




## Challenge

- **4.5 MHz frame rate**
- Efficient detectors
- 2-dimensional pixel detectors
- single photon sensitivity
- integrating large number of counts
- high count rate effects
- **enormous data rates**
- **large data volumes**





# 2D pixel detector developments





## AGIPD Adaptive Gain Integrating Pixel Detector

- ⇒ dynamic gain switching
- ⇒ 1 analog pipeline

collaboration:

DESY, PSI, U Bonn, U Hamburg





## LPD Large Pixel Detector

- ⇒ large dynamic range
- ⇒ 3 analog pipelines

collaboration:

STFC/RAL, U Glasgow





## DSSC DEPFET



- ⇒ non-linear amplification
- ⇒ soft x-ray sensitivity

collaboration:

MPI-HLL, U Heidelberg, U Siegen, DESY, Politecnico die Milano, U Bergamo



# Under study: New parameter set accelerator




Parameter	Unit	Value
Electron energy for 0.1 nm FEL radiation	GeV	14
Accelerating gradient	MeV/m	24.3
Bunch charge	nCb	0.02 – 1
Peak current	kA	2 – 5
Normalized slice emittance (rms)	mm mrad	0.4 – 1.0
Electron energy spread (rms)	MeV	4 – 2
RF pulse repetition rate	Hz	10
Repetition rate during RF pulse	MHz	4.5
Max. number of electron bunches per RF pulse		2700
Duration of electron bunchtrain	μs	600





- Coherent diffraction imaging from injected particles
- Time-resolved diffraction from (aligned) gas molecules




- UHV vacuum system to suppress background scattering on 2D detector
- various sample injectors (liquid jets, droplets, aerosols) & cryo-stage
- sample & beam diagnostics (emission, ion-spec, dedicated samples)



# Soft x-ray Coherent Scattering – SCS

- Coherent diffraction imaging from nano-structured samples
- X-ray photon correlation spectroscopy of nanoscale dynamics
- Spectroscopy applications



- use one beam delivery system and sample stage
- use detector at different distance and up to large angles
- sample damage is an issue for resonant absorption (magnetic studies)